



ALMA Overview and Status

ALMA Community Days 2015

Wolfgang Wild

European ALMA Programme Manager





ALMA Overview




- Aperture synthesis array for (sub)mm wavelengths of 10 mm – 0.3 mm (35 – 950 GHz)
- High, dry site, Chajnantor Plateau, Chile (5000m)
- 66 antennas (54 x 12m + 12 x 7m)
- Baselines from ~15 m to 16 km
- Resolution/arcsec $\approx 0.2(\lambda/\text{mm})/(\text{max baseline}/\text{km})$
 - 5 mas for highest frequency/longest baseline
- Field of view / arcsec $\approx 17 (\lambda/\text{mm})$ [12m dish]
- Sensitive, wide-band (8 GHz) receivers; full pol.
- Flexible digital correlator giving wide range of spectral resolutions.








ALMA Configurations



Most compact configuration
($d \sim 150\text{m}$): 0.5" ... 5"

Demonstrated in 2014:
most extended configuration
(max 16km): 0.005" ... 0.05"





OSF – Operations Support Facility



ALMA Residence
(under construction)

- Altitude 2900 m
- ALMA control room
- Technical labs
- Dormitories & canteen




Receiver Bands




ALMA Band	Frequency Range (GHz)	Receiver Noise (K) over 80% of the RF band	Temperature (K) at any RF Frequency	produced by	Receiver Technology
1	31 - 45	17	26	tbd	HEMT
2	67 - 90	30	47	tbd	HEMT
3	84 - 116	37	60	HIA	SIS
4	125 - 163	51	82	NAOJ	SIS
5*	162 - 211	65	105	NOVA/OSO	SIS
6	211 - 275	83	136	NRAO	SIS
7	275 - 373	147	219	IRAM	SIS
8	385 - 500	196	292	NAOJ	SIS
9	602 - 720	175	261	NOVA	SIS
10	787 - 950	230	344	NAOJ	SIS

* Full Band 5 production from 2013 – 2017, Bands 1 and 2 TBD




Band 7 Performance

■ Sensitivity ~2 times better than specification



Band 9 Performance

■ Sensitivity up to 2 times better than specification





Construction Status



- Construction formally finished end of 2014
 - All 66 antenna elements equipped with 7 rx bands
 - Construction accounts mostly closed
 - Manufacturer warranty mostly expired

- Some items are ongoing
 - CSV/EOC (Extension of Capabilities)
 - Construction of ALMA Residence (ESO)
 - Vertex antenna astigmatism (NRAO)
 - Front End Handling Vehicle (NRAO)
 - ACA correlator topics (NAOJ)



Finalization of Modes needed for Full Operations



(From: S. Corder et al., 2015, final draft, “ALMA Transition To Steady State and Full Operations”)

- Long baseline capability [COMPLETE]
- All construction bands [COMPLETE]
- Solar observing
- Final polarization modes
- Improvements needed at high frequency
- Final implementation of single dish capabilities
- Long integration capability (at least 24 hours)
- Repeatable precision observations



ALMA Residence



- Last deliverable of ESO
- Modular concept with 6 dormitory buildings





ALMA Residence





Residence Construction started




- In February 2015, the construction of the ALMA Residence has started, ongoing heavy earth works
- Construction duration ~18 months



- 0 – 90° astigmatism, amplitude \propto temperature
 - Cabin deformation + yoke
 - Known at acceptance, but coefficient underestimated
 - Correct value $d(\text{rms})/dT \approx 0.7\mu\text{m}/\text{K}$ (tower and astro-holography) due to astigmatism alone
 - Antenna surfaces are optimized at $\approx 7\text{C}$, rather than mean ops temp
 - Surface is typically out of specification ($>25\mu\text{m}$ rms) at low temperatures (= best night-time conditions)
 - Efficiency typically $\sim 20\%$ lower than AEM/Melco antennas at 690GHz

■ Corrective action

- Optimize surface correctly for -5C
 - Antennas in specification under almost all night-time conditions
 - Straightforward at OSF
 - More efficient at AOS, but riskier
- Use local heating to fix the problem
 - needed for daytime operation
 - under investigation





ACA Correlator



- Three technical issues (info from EA PM)
 - 3-bit linearity correction
 - Robustness improvement
 - Subarray mode
- Work is in progress
 - Verification at AOS (except subarray mode) ongoing, firmware problems found
 - No big impact for Cycle 2 obs. and science capabilities
 - Resolution before start of Cycle 3 (except Subarrays)
- Subarray mode
 - No issue for Cycle 3, plan to resolve it for Cycle 4



Development Projects



- **Band 5 (167-211GHz) full production (EU-led)**
 - NOVA/Chalmers/NRAO (2013-2017)
 - Integration of first cartridge at OSF this month
- **Fibre connection OSF – Santiago (JAO-led)**
 - Technically complete, permits pending
- **ALMA phasing project/VLBI (NA-led)**
 - Technical implementation ongoing, aim to offer it in Cycle 4, operations model under discussion
- **Band 1 (EA-led)**
 - Building & testing prototype receiver
- **Band 2 prototype (NA), Band 2&3 study (EU)**

